

BRUHAT BANGALORE MAHANAGARA PALIKE


Item No.38

APPROVED SCHEDULE - B

Tender Notification No: EE(BTP)/TN/GL- 06/2012-13 Dated:10.09.2012

Name of Work:Improvements to Cross Roads and Drains at Kuvempunagara 1st Stage in Ward No. 11, Vidyaranyapura Sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of	
				Hombe Gowda	
				In Figures	In Words
1	170.06	Earth work excavation by manual means in Hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	85.01	Rupees Eighty Five Only
2	95.37	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180 Kgs using 40mm and down size graded granite metal, coarse aggregates @ 0.85 cum and fine aggregates @ 0.58cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4077.06	Rupees Four Thousand Seventy Seven and Five Paise Only
3	261.90	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness , including attached pilasters, buttresses, plinth and string courses cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work	Sqm	256.16	Rupees Two Hundred Fifty Six and Sixteen Paise Only
4	30.07	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 Kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878cum and fine aggregates @ 0.459 cum with superplasticiser @ 3lts confirming to IS 9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, wall (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5498.41	Rupees Five Thousand Four Hundred Ninety Eight and Forty One Paise Only



Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of	
				Hombe Gowda	
				In Figures	In Words
5	18.04	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery etc complete as per specifications and directions of engineer in charge of the work	Qntl	7685.99	Rupees Seven Thousand Six Hundred Eighty Five and Ninety Nine Paise Only
6	55.00	Providing & fixing 20 mm thick compressible fibre board in expansion joint complete as per drawing & technical specification etc complete as per specifications and directions of engineer in charge of the work	M	139.42	Rupees One Hundred Thirty Nine and Forty One Paise Only
7	42.00	Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300 kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.64 cum and fine aggregates @ 0.43 cum with superplastisiser @ 3lts confirming to IS9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5182.18	Rupees Five Thousand One Hundred Eighty Two and Seventeen Paise Only
8	420.00	Vaccum De-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator HOM of machinery Screed Vibratory, Power Floater, blade and disc etc complete as per specifications and directions of engineer in charge of the work	Sqm	90.68	Rupees Ninety and Sixty Seven Paise Only
9	144.55	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means including loading and unloading etc complete as per specifications and directions of engineer in charge of the work	Cum	76.31	Rupees Seventy Six and Thirty Paise Only



Signature of the Contractor


Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92